

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Washtenaw

Located in: SALINE Corner Code

County

Public Land Survey

T	4	S	R	5	E	K-9
T			R			
T			R			
T			R			
T			R			

Property Controlling in Section

S		T	R			
S		T	R			

Miscellaneous

S		T	R			
---	--	---	---	--	--	--

Property in Sec.

S		T	R			
---	--	---	---	--	--	--

LIBER 1 PAGE 361 RM COPY Register of Deeds Stamp and File Number

Lot No. _____, Recorded Plat _____ Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Michael S. Hoben in a field survey on 08/30/1994 I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restorations: 07/21/1819 G.L.O. SET POST 4" ASH S 38 E 12 LINKS 10" ASH N 48 W 13 LINKS

(Witnesses Continued on Back ...)

Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1/2" IRON PIPE

Description of monument for corner and accessories established to perpetuate locating the position of the corner: 08/30/1994 HOBEN 35449 O.H.M. REMON.

- SET W.C.R. CAP INSIDE IRON
- 1 P.K. NAIL W/W.C.R. TAG ON N. SIDE P.P. S 70 E 95.79'
- 2 P.K. NAIL W/W.C.R. TAG ON N. SIDE P.P. S 88 W 193.55'
- 3 S. FACE STEEL FENCE POST N 32 E 36.38'
- 4 SET 1/2" IRON ROD WITH RED CAP S 52 E 34.77'

RECORDED WASHTEENAW COUNTY, MI FEB 1 8 53 AM '95 PEGGY M. HAINES COUNTY CLERK/REGISTER - COPY -

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Witnessed by Michael S. Hoben Date Dec 1994 Surveyor's Michigan License No. 35994 Richard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150



A. (Continued) Description of original monument and accessories and/or subsequent restorations:

05/05/1936 ARMSTRONG 1244 W.C.R.C.

RESTORED TO FIT
OCCUPATION - DOSE NOT
MENTION WHAT WAS SET
OR ANY WITNESSES.

1 24" B. WALNUT N 3 W 192.2'

2 14" B. WALNUT S 75 E 114.0'

06/03/1968 FAHRNER 17620 W.E.

SURVEY FD. IRON PIPE

USED DWG. IN ADJECENT SECTION TO FIND K-09

2

APPROVED
DATE 12/19/24
REP. KJ