

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAY - 1 1995

K-11 Page 1

COMMISSION

For corners in

Washtenaw

Located in: SALINE Corner Code

County

- 1. Public Land Survey T 4 S R 5 E K-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1852 1 PAGE 364 RM
COPY

Register of Deeds Stamp and File Number

Michael S. Hoben in a field survey on 06/08/1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restorations:

07/21/1819 G.L.O. SET POST
13" LILIAC N 67 W 35 LINKS
12" ELM S 35 E 22 LINKS

(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1 1/2" IRON PIPE 8"
UNDER SURFACE OF
GRAVEL ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

06/08/1994 HOBEN 35994 O.H.M. REMON
SET REMON. CAP INSIDE 1 1/2" IRON PIPE
1 D.E. POLE P.K. NAIL W/WCR TAG N 35 E 62.02'
10 P.K. NAIL W/WCR TAG IN 8" OAK S 75 W 118.65'
11 8" WOOD POST P.K. NAIL W/WCR TAG S45 E 35.28'
12 P.K. NAIL IN 4" OAK W.WCR TAG S 20 E 89.90'

RECORDED
WASHTENAW COUNTY, MI
FEB 1 8 54 AM '95
PEGGY M. HAINES
COUNTY CLERK/REGISTER
-COPY-

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by Michael S. Hoben
rafted by Michael S. Hoben
urveyor's Michigan License No. 35994
rched, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

Date Dec 29 1994



