

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Washtenaw

Located in: SALINE Corner Code

County

Public Land Survey

T 4 S R 5 E	M-11
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Property Controlling

in Section

Miscellaneous

Property in Sec.

1 PAGE 380 RM COPY

Register of Deeds Stamp and File Number

Lot No. _____, Recorded Plat _____ Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Michael S. Hoben in a field survey on 06/07/1994 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restorations:

11/29/1815 G.L.O. SET POST 12" W.O. S 32 E 61 LINKS 12" W. O. N 3 W 1.56 CH.

(Witnesses Continued on Back ...)


Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1" IRON PIPE, RESET WITH W.C.R. CAP OVER IRON, 6" DEEP

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

06/07/1994 HOBEN 35994 O.H.M. INC. REMON SET W.C.R. CAP OVER IRON 3 STUMP 296 +/- S52E' 5 TO IRON 136.90 6 PK NAIL WITH WCR TAG ON NW SIDE P.P. S8E 107.95' (R) 7 PK NAIL WITH WCR TAG (R) ON NW SIDE P.P. N42 E 44.46' 10 END OF 12" CULVENT N87W. 20,20'

RECORDED WASHTEHAW COUNTY, MI FEB 1 8 57 AM '95 PEGGY M. HAINES COUNTY CLERK/REGISTER -copy-



I conclude that after careful study of the record documentation and field observations, that this corner is accepted as best available evidence of the position of the original corner.

Witnessed by Michael S. Hoben Surveyor's Michigan License No. 35994

Date Dec 29 1994

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

11/29/1815	G.L.O.			SET POST
1	MEASURED TO DOUBLE CORNER SOUTH 2.12 CH (139.92')			
04/17/1934	ARMSTRONG	1244	W.C.R.C.	DOSE NOT STATE WHAT WAS FOUND
2	SW COR OF S. END OF W. CULV. HEADWALL N 65 W 9.6'			
3	SE COR OF S. END OF E. CULV. HEADWALL N 63 E 9.9'			
4	14" MAPLE S 52 E 296.4'			
5	24" MAPLE S 6 E 173.6'			
08/31/1981	FAHRNER	17620	W.E.C. L.6,P	FD. 1" IRON PIPE
1	SW COR. SEC. 30 T.4,R.6E SOUTH 140.24'			
4	24" MAPLE S 52 E 296.4'			
6	P.P. S 10 E 108.37' TO NAIL			
04/30/1993	JEKABSON	19836	SURVEY	DOSE NOT STATE WHAT WAS FOUND.
	MEAS. TO M-12 2644.96'			

APPROVED

DATE 12/19/94

CO. REP. KJ

2