

APPROVED

DATE 9-23-96

CO. REF. KA

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
WASHTENAW COUNTY, MICH.
FEB 18 9 19 AM '97
PEGGY M. HAINES
COUNTY CLERK/REGISTER

For corners in

WASHTENAW
(county)

Located In: Corner Code #

- 1. Public Land Survey T 4S R 6E H-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Liber 00001 Page 0658 RM

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, PATRICK L. HASTINGS, in a field survey on FEB. 29, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1819 G.L.O. SET WOOD POST
7" POPLAR N 85° W 7 LKS
14" SYCAMORE S 72° E 15 LKS
- 1934 GRID BOOK SHOWS NOTHING.

(CONTINUED ON BACK)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996 FOUND 3/4" IRON PIPE ON OCCUPATIONAL FENCE LINE TO EAST AND CROP LINES TO NORTH AND WEST. PULLED IRON AND DUG FOR OTHER EVIDENCE. FOUND NOTHING.
- 1) 18" TWIN OAK EAST 54.78
- 2) 22" TWIN OAK EAST 62.78
- 3) 4"X6" FENCE POST S 85° E 0.9'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

AFTER A CAREFUL STUDY OF THE RECORD DOCUMENTATION AND FIELD OBSERVATIONS, MADE UNDER MY DIRECT SUPERVISION. I FIND THIS CORNER TO BE THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. THE 3/4" IRON PIPE WAS CAPPED WITH A REMONUMENTATION CAP STAMPED #37277

- 1) 18" TWIN OAK EAST 54.78 PK/RT
- 2) 22" TWIN OAK EAST 62.78 PK/RT
- 3) 4"X6" FENCE POST S 85° E 0.9'
- 4) 8" HACKBERRY S 85° W 6.28' PK/RT



COPY

Signed by Patrick L. Hastings
Surveyor's Michigan License No. 37277

Date 10/28/96

NO DATE- ATWELL-HICKS COMPILED SURVEY DRAWING NOTES THE FOLLOWING:

"WASHTENAW ENG. CO., BOOK 2, PG. 14, 4" SQ. TOP SANDSTONE."

NOTE: CALLED WASHTENAW ENGINEERING, THEY DON'T HAVE A BOOK #2.
I BELIEVE THIS REFERENCE IS TO AN OLD COMPANY ALSO KNOWN
AS WASHTENAW ENGINEERING, NOW OUT OF BUSINESS.

- 1971 SURVEY BY ATWELL-HICKS, JOHN LITCHFIELD SNYDER P.S. #13352, LIBER 1370, PG. 383
FOUND IRON PIPE.
(1) 14" TWIN OAK EAST 55.0
(2) 14" TWIN OAK EAST 63.0
- 1989 SURVEY BY LAND SURVEYING CONSULTANTS, R. TIMOTHY TIETSEMA P.S. #20712,
JOB #06888-4S6E34. FOUND 1" IRON PIPE.
(1) 24" OAK EAST 55.6
(2) 36" TWIN OAK EAST 63.7
(3) 4"x6" POST S 45° E 1.1
- 1992 SURVEY BY LAND SURVEYING CONSULTANTS, R. TIMOTHY TIETSEMA P.S. #20712,
JOB #004792-4S6E34. FOUND 1" IRON PIPE.
(1) 24" OAK EAST 55.6
(2) 36" TWIN OAK EAST 63.7
(3) 4"x6" POST S 45° E 1.1