



SECTION 'A' CONTINUED

No Date	(5) S 87° W	57.1'	12" Hickory
	(6) East'ly	22.7'	West edge of sidewalk
1934	W.C.R.C. Gridbook by F. Colburn for C.W.A.		
	(4) N 30° E	56.1'	15" B. Cherry
	(7) S 35° W	61.3'	6" Cherry
	(8) N 52° W	69.3'	10" Hickory
	(9) S 88° E	33.3'	40" Br. Elm
	(10) S 66 1/2° E	22.0'	Top of fire hydrant
1971	Survey by H.W. Goodwin, L.1381, pg. 335.		
	(1) South	520.35'	Iron at centerline Platt & Saline Milan Rds.
1972	Plat, Capps Colony Complex by C.O. Thomas, File No. 53788		
	(1) S 01° 05' 20" E	520.49'	Iron X" Platt & Milan
	(11) S 89° 25' 05" E	33.00'	Set require monument
1981	L.C.R.C. by N. N. Fahrner, found iron pipe L. 6, pg. 101		
	(3) N. E'erly	34.6'	18" Ash
	(12) S 87° W	68.9'	20" Oak
	(13) S 40° W	97.6'	27" Maple
1981	Survey by Washtenaw Engineering. Shows corner.		
1984	Survey by Dزيدris Vitins of Orchard, Hiltz & McCliment. Found iron as recorded, L. 6, pg. 101.		
	(1) Due South	520.49'	"X" Platt & Saline-Milan Roads
1989	Witnesses by Roskelly.		
	(3) N 45° E	34.6'	18" Ash, nail in S. side
	(12) S 80° W	68.9'	30" Oak, nail in E. side
	(13) S 40° W	97.7'	27" Maple, nail in N.E. side
1990	Oct. 13 Survey by J. Blanchard shows corner		
1992	Survey by R. T. Tietsema, found 1/2" rebar.		
	(3) N 45° E	34.6'	18" Ash, nail in S. side
	(12) S 80° W	68.9'	30" Oak, nail in E. side
	(13) S 40° W	97.7'	27" Maple, nail in N.E. side
	(14) West	33.01'	1/2" iron rod for R/W Cap #20712, R.T.T.

SECTION 'B' CONTINUED

1993	(4) N 35° E	55.10'	24" Wild cherry to 20 P spike
	(15) East	60.92'	Set Pk in north face utility pole
	(16) S 42° E	31.00'	Top nut hydrant
	(17) S 80° W	30.72'	Fd. Pk nail in S. face telephone

Searched for R/W monument at N.W. corner of "Capps Colony Complex". Apparent recent water work in area, monument lost.

SECTION 'C' CONTINUED

(4) N 35° E	55.10'	24" Wild cherry to 20 P spike & R.T.
(14) West	33.01'	1/2" iron rod for R/W, cap #20712, R.T.T.
(15) East	60.92'	Set Pk & R.T. in north face utility pole
(16) S 42° E	31.00'	Top nut hydrant
(17) S 80° W	30.72'	Pk nail & R.T. in S. face telephone

APPROVED  
DATE 2/22/94  
CO. REP. Y/A