

SECTION 'A' CONTINUED

1962 July 5 - Atwell-Hicks, Inc.; Field notes

At S 1/4 corner of Section 26, found R.W. iron on N. side of road. Mea. sly 33' dug hole 2.5 x 2 x 5 x 2.5 hole found many pieces of brick and tile but could find no iron. Found piece of 3" tile standing vertical - followed dark mark down 6" - set 1 1/2" x 36" iron where dark mark went down - this was also next to large rock.

(3)	N'ly.	33.0'	To R.W. iron
(5)	S'ly.	76.6'	10" Elm
(6)	N 50° W	85.7'	P.P.
(7)	N 50° E	113'	To S.E. trunk of mulp. 12" mulberry tree

No Date Survey by Wash. Eng. Co.; shows corners as found.
West 2656.00' Corner common 27, 26 & 34, 35

1972 L.C.R.C. by N.C. Jones #02934, L.2, pg. 371; found 3/4" pipe buried 6" below surface (No witnesses listed in Section "B").

(6)	N 62° W	85.84'	P. Pole
(7)	N 78° E	113.50'	Clump mulberry
(8)	S 04° W	36.45'	6" Ash

1973 L.C.R.C. by A.C. Crossman #9428, L.3, Pg. 435, Found 3/4" iron pipe (no witnesses listed in Section "B").

(3)	North	32.90'	R/W Iron on east side of fence post
(6)	N 70° W	85.75'	Edison poles, P.K. nail S. side
(7)	N 75° E	113.45'	Tree clump. Nail and cap in S. side
(9)	North	32.20'	Fence post, nail in E. side

SECTION 'B' CONTINUED

Found 1" iron pipe badly bent to the east and 1" below crushed limestone surface of Arkona Road.

Excavated to a depth of 6" and found a disturbed nail on the west side of the iron. The iron appeared to straighten out here and I witnessed the apparent center to four P.K. nails set at three feet in the cardinal direction. Hole size, 18" x 18".

Excavated to a depth of 14" and found broken brick and bits of iron which appear to be broken mushroom from the top of the pipe. The pipe takes a slight bend to the southwest.

Excavated to 18" and found the top of unbroken brick and stone. I removed the pipe to find it closely resembles a dog's hind leg and has a total length of .25".

The bottom of the hole, left after the pipe was removed, was 0.09' south and 0.12' west of our witness location of the apparent center at a depth of 6".

Making note of the witness measurements to the bottom of the hole left by the pipe, I set a 1" x 24" iron pipe and Washtenaw County Remonumentation cap stamped #37277, the top of which is 7" below surface.

On December 27, 1993, while making a preliminary inspection of this corner location, I found the north R/W iron pipe, 1" x 24", was on the surface, S.W. 10'. Plowed out this past fall. I also found an old "chain drive gear", of the kind typically found on old farm machinery, at a depth of 1' and 33'± north of the bent corner.

I set the instrument on the remonumented corner and backsighted the 1" iron pipe for the south R.W. which measured 33.02'. I extended this line north 33' and excavated carefully to a depth of 18" upon finding pieces of rusty iron flakes that look like those remaining on the iron I found lying on the surface. I reset this same iron at 33.00' and drove it so it's top is 14"± below the surface. I then placed the old "chain drive gear" around the pipe and backfilled the hole.

Measured West 2655.55' corner common 27, 26 and 34, 35.

SECTION 'C' CONTINUED

Set a 1" x 24" iron pipe and Washtenaw County Remonumentation Cap Stamped #37277.

(3)	North	32.00'	1" x 24" R/W iron, reset
(4)	South	33.02'	1" R/W iron, found
(6)	N 68° W	85.69'	R.T. & P.K. in power pole
(7)	N 78° E	113.14'	R.T. & P.K. in mulberry clump Avg. 12"
(10)	S 19° E	34.70'	R.T. & P.K. in 6" elm
(11)	S 81° W	124.65'	R.T. & P.K. in 22" poplar

APPROVED
DATE 3/22/94
CO. REP. KJ