

REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|----|------|
| 1. Public Land Survey | T | 4S | R | 6E | M-11 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Sec. | S | | T | | |
| | S | | T | | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
WASHTENAW COUNTY, MI
 SEP 21 11 20 AM '94
 PEGGY M. HAINES
COUNTY CLERK/REGISTER
 LIBER 1 PAGE 76Rⁿ
 -COPY-
 Register of Deeds Stamp & File Number

I, Patrick Hastings, in a field survey on December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1815 G.L.O. Survey Notes by: Set post
Beech 12" N 20° E 38 lks
Elm 24" S 60° E 25 lks
- 1819 G.L.O. Survey Notes by: J. Francis; Intersected range line 50 lks south of post at 80.50 chains
- 1934 W.C.R.C. by W.J. Armstrong: Found a piece of pointed sandstone. Reset with a 1 1/2" x 42" iron pipe and put stones and bricks around it.
(1) N 03° E 119.2' 12" Maple
(2) N 56° E 147.0' 12" Ash

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993 Found 1 1/2" iron pipe 4" deep surrounded by brick and stone, in good condition.
- (1) From survey by H. Woodwin dated: 9-22-1971
Found iron 213.8 west
Found C/L of conc. rod south 181.7'
Found 1/2" rebar and cap #8102, south 225.0
Accepted as a perpetuated corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

After a careful study of the record documentation and field measurements, made under my direct supervision, I find this corner as remonumented to be the best available evidence of the position of the original corner.

Set a 1" x 6" iron pipe and standard remon. cap stamped 37277 in the found 1 1/4" iron pipe.

- | | | | |
|-----|---------|---------|--|
| (1) | N 03° E | 119.20' | 30" Maple. Set P.K. & R.T. in E. face at record distance |
| | N 85° E | 29.81' | Railroad tie corner post, set P.K. & R.T. in top. |
| | S 15° W | 89.00' | 12" Apple. Set P.K. & R.T. in E. face |
| | N 65° W | 42.29' | 26" Maple. Set P.K. & R.T. in N. face |



Signed by Patrick L. Hastings Date 6/27/94
Professional Surveyor's Michigan License No. 37277

LIBER 1 PAGE 77Rm
- COPY -

SECTION 'A' CONTINUED

1934	(3)	N 33° E	20.0'	28" Maple, to iron pin in tree
	(4)	North	33.0'	1 1/2" iron pipe
1969				Survey by N. Fahrner: F.I.P.
1971				Survey field notes by: A. Butterfield. Found 1 1/2" pipe
1971				Survey by H. Goodwin: Found iron pipe.

APPROVED
DATE 2/8/94
CO. REP. K₂