

RECORDED
 NOV 20 2000

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW
 (County)

Located In: T 4S R 7E Corner Code # G-9

1. Public Land Survey AUGUSTA TWP
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property controlling in Section
 S _____ T _____ R _____
 S _____ T _____ R _____


3. Miscellaneous Property in Sec.
 S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

5094708
 Page: 1 of 2
 02/07/2000 02:55P
 L-2 P-290
 Peggy M. Haines - Washtenaw Co. CORREM
 Register of Deeds Stamp & File Number

I, LORI E. BEYER, in a field survey on NOVEMBER 20, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:



1999 REMONUMENTATION CORNER


A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. - JOSEPH FRANCIS - 1819
 SET POST
 10" BEECH S 08° W 10 LINKS
 16" ASH N 09° W 29 LINKS

Continued on Back

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:
 FOUND 3/4" IRON PIPE AT ROAD SURFACE IN THE INTERSECTION OF WHITTAKER AND WILLOW ROADS.
 CHECKED WITNESSES. RESET WITH MONUMENT BOX AND 3/4" x 24" IRON PIPE AND ALUMINUM REMON. CAP STAMPED '41092'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 3/4" x 24" IRON PIPE WITH ALUMINUM REMON. CAP STAMPED '41092' IN MONUMENT BOX IN THE INTERSECTION OF WHITTAKER AND WILLOW ROADS.

- | | | | |
|----------------------------|---------|--------|-----------------------------------|
| 4) UTILITY POLE | N 50° E | 40.52' | SET NAIL/TAG SE SIDE |
| 9) UTILITY POLE | S 35° E | 46.99' | SET NAIL/TAG EAST SIDE (NEW POLE) |
| 6) CORNER STEEL FENCE POST | S 46° W | 47.2' | |
| 10) UTILITY POLE | S 45° W | 45.16' | SET NAIL/TAG WEST SIDE |
| 11) 3" MAPLE | N 49° W | 73.75' | SET NAIL/TAG EAST SIDE |



AFTER CAREFUL EXAMINATION OF RECORD DOCUMENTATION AND FIELD OBSERVATIONS, I BELIEVE THIS POINT SHOULD BE ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.
 THIS CORNER WAS RATIFIED BY THE PEER REVIEW COMMITTEE ON NOVEMBER 22, 1999.

Signed by Lori E. Beyer
 Surveyor's Michigan License No. 41092

APPROVED
 DATE 11/21
 CO. REP. K
 Date Dec 03, 1999

G-9 CONTINUED FROM PARAGRAPH A

WASHTENAW COUNTY GRID BOOK - NO WITNESSES POSTED - SURVEYOR UNKNOWN - DATE UNKNOWN
MONUMENT NOT DESCRIBED

- | | | |
|-------------------------|---------|--------|
| 1) NW COR S. CULV. HDWL | S 85° E | 75.95' |
| 2) 12" CHERRY | S 45° W | 50.1' |
| 3) 24" POPLAR | N 30° W | 44.4' |

L.C.R.C. LIBER 7 PAGE 69 - ROBERT CAMPBELL JR. #13028 - JUNE 1984

FOUND 1" IRON PIPE AT ROAD SURFACE. ALL OLD WITNESSES GONE. DID NOT FIND ANY OTHER IRONS IN INTERSECTION PRIOR TO CONSTRUCTION. RESET AFTER CONSTRUCTION WITH 3/4" X 18" IRON PIPE AND AND CAP IN THE INTERSECTION OF WHITTAKER AND WILLOW ROADS.

- | | | | |
|------------------------|---------|--------|--------------------|
| 4) TELEPHONE POLE | N 53° E | 41.75' | SET NAIL S. SIDE |
| 5) TELEPHONE POLE | S 24° E | 65.08' | SET NAIL WEST SIDE |
| 6) CORNER FENCE POST | S 52° W | 47.1' | |
| 7) CONCRETE R/W MARKER | N 56° W | 54.1' | |
| 8) 3" BOXELDER | N 47° W | 72.5' | |



5094708

Page: 2 of 2
02/07/2000 02:55P

Peggy M. Haines - Washtenaw Co. CORREM L-2 P-291

Copy

SURVEY &
RECORDS SECTION

MAY 20 2000

SECTION