

MAR 09 1998

RECORDED
WASHTENAW COUNTY, MI

SECTION

JAN 22 8 38 AM '98

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PEGGY W. HAINES
COUNTY CLERK/REGISTER

For corners in
WASHTENAW
(county)

Located In: Corner Code #

- 1. Public Land Survey T 4S R 7E J-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- COPY -

- COPY -

Liber 00002 Page 0127 RM

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PATRICK L. HASTINGS, in a field survey on NOV. 24, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1819 G.L.O. Field Notes and Plat
Set Post
1) N 20° W 17 LKS W.O. 40'
- 1935 W. J. Armstrong, W. C. Lowe.
Found a wood stake with 4 bricks set around it on end to form a box.
Reset by driving an iron pipe into the stake.
2) N 35° E 45.1' Apple 10"
3) N 51° W 40.4' Elm 12"
4) N 43° W 41.1' W. Oak 4"
5) N 37° W 53.3' W. Oak 10"
6) North 31.7' Ironwood 4"

2 Right-of-Way Pipes (SECTION A CONTINUED)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" iron pipe surrounded with brick witnessed iron and pulled. Dug and found no other evidence. No remaining witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1 1/2" iron pipe with 1"x18" iron pipe with remon. cap stamped #37277.

- N 70° E 217.70' 14" SYCAMORE
- N 15° E 33.40' UTIL POLE WITH NAIL
- N 35° W 93.00' 18" OAK WITH NAIL
- N 55° W 107.00' 19" OAK WITH PK
- S 58° W 71.10' 12" OAK WITH NAIL

APPROVED
DATE 11/24/97
CO. REP. [Signature]

After a careful study of the record documentation and field observations, made under my direct supervision, I find this corner as remonumented to be a careful and faithful perpetuation of the position of the original corner.

Signed by [Signature] Date 11/24/97

Surveyor's Michigan License No. 37277

- COPY -

SECTION A CONTINUED

- 1972 Three surveys by Glenn E. Richard #13040
From Associated Engineers and Surveyors, Inc.
Same witnesses on both surveys. Found Iron Pipe.
- | | | | |
|-----|---------|---------|----------------------|
| 7) | N 40° E | 41.70' | Nail in Edison Pole |
| 8) | S 80° E | 129.36' | Nail in Sycamore 16" |
| 9) | S 50° E | 38.85' | Nail in Sycamore 16" |
| 10) | S 80° W | 110.95' | Nail in Sycamore 20" |
- 1972 L.C.R.C. by Glenn E. Richard #13040
From Associated Engineers and Surveyors, Inc.
- | | | | |
|-----|---------|---------|----------------------|
| 7) | N 40° E | 41.70' | Nail in Edison Pole |
| 8) | S 80° E | 129.36' | Nail in Sycamore 16" |
| 9) | S 50° E | 38.85' | Nail in Sycamore 16" |
| 10) | S 80° W | 110.95' | Nail in Sycamore 20" |
- 1994 Right-of-way survey by Midwestern Consulting, Inc. Corner shown by
symbol with distances to the hundredth of a foot. Corner was found
using previous surveyor's witnesses.