

MAR 09 1998

SECTION

RECORDED  
WASHTENAW COUNTY, MI

JAN 22 8 38 AM '98

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW (county)	Located In:	Corner Code #
1. Public Land Survey	T 4S R 7E	J-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PEGGY J. HAINES  
COUNTY CLERK/REGISTER

- Copy -

Liber 00002 Page 0129 Rm  
- Copy -  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PATRICK L. HASTINGS, in a field survey on NOV. 24, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1819 G.L.O. Field Notes and Plat.  
Set Post in creek.  
no witnesses
- 1935 Armstrong attempted to recover J-13 but notes it was lost during the construction of the new drain. His notes indicate he chained along the south line of sections 33, 34 35, and 36 he calls out the S 1/4 corner of section 35 but does not state whether he found it, or set it, nor does he provide any witnesses.
- 1976 Walter E Frazier and Associates survey shows S 1/4 corner.  
1) N 45° W 41.35' 30" tri. maple  
2) S 05° E 9.61' 12" w cherry  
note: I called Ken Suydam he stated that he set J-13 in a rotted wooden post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Using the Frazier survey we established a search area for J-13. We dug and found a bent 1" iron pipe. During the excavation we found the remains of an old wire fence, we dug east and west and found more remains of the fence.

- 1) N 45° W 39.80' 32" tri. maple



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1" iron pipe with 1"x 24" iron pipe with remon. cap stamped 37277

- 1) N 45° W 39.80' 32" tri. maple (PK & RT)
- S 62° W 30.85' 12" W. OAK (PK & RT)
- S 20° W 32.60' 18" SYCAMORE (PK & RT)
- S 65° E 34.50' 12" W. OAK (PK & RT)
- N 50° E 47.50' 14" W. OAK (PK & RT)

APPROVED  
DATE 12-2-97  
CO. REP. *[Signature]*

After a careful study of the record documentation and field observations, made under my direct supervision, I find this corner as monumented to be a careful and faithful re-establishment of the position of the original corner.

Signed by *[Signature]* Date 12/2/97

Surveyor's Michigan License No. 37277