

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

COPY

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Washtenaw</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>4S</u> R <u>7E</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 388 RM
COPY
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Thomas L. Sutherland in a field survey on November 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(W.C.R.C. 1930)	(Atwell-Hicks 1973)	(Washtenaw Engineering 1975)
Found 1 1/4" Iron Pipe which had been driven into the center of a wood stake and was surrounded by bricks.	12" W. Pine N64°W 79.8 28" R. Oak N17°W 70.8 40" R. Oak S60°E 89.3 Power Pole S38°E 43.2	30" Oak S68°E 89.30 to Nail E. Pole SE 43.2 to Nail Guy Pole SW 50.75 to Nail
16" Oak S68°E 89.35		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron Pipe at asphalt surface over 1/2" Iron Pipe inside 1 1/4" Iron Pipe 24" below asphalt surface. Also found bricks 24" below asphalt surface. Reset 1" Iron Pipe with Aluminum Washtenaw County Remonumentation Cap over existing 1/2" Iron Pipe. Set Monument Box over Pipe.

RECORDED
WASHTENAW COUNTY, MI
FEB 1 8 59 AM '95
PERCY M. MAINES
COUNTY CLERK/REGISTER
- COPY -
APPROVED
DATE 11/21/94
CO. REP. KA

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" x 24 Iron Pipe with Aluminum Washtenaw County Remonumentation Cap in Monument Box
40" Oak N68°E 89.25 to Nail W/W.C.R. Tag in N.E. Side
24" White Pine N64°W 79.80 to Nail W/W.C.R. Tag in N.E. Side
Power Pole S38°E 43.20 to Nail W/W.C.R. Tag in N.E. Side
Power Pole N60°W 65.54 to Nail W/W.C.R. in S.W. Side
20" Poplar S43°W 49.62 to Nail W/W.C.R. Tag in S.E. Side

Triple 10" Apple N45°E 64.68 to Nail W/W.C.R. Tag in N. W. Side

I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of position of the original corner.

Signed by Thomas L. Sutherland Date December 13, 1994
Surveyor's Michigan License No. #24620

