

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

COMMISSION

COPY

RECORDED
WASHTENAW COUNTY, MI

FEB 1 8 59 AM '95

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Washtenaw</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>4S</u> R <u>7E</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PEGGY M. HAINES
COUNTY CLERK/REGISTER

- COPY -

LIBER

1 PAGE 389 RM
COPY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Thomas L. Sutherland in a field survey on November 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(W.C.R.C. 1932)
Found an old wood stake and a square boat spike 20" long surrounded by bricks and re-set with a 2" x 48" Iron Pipe and put 4 bricks around it.
2 Right-of-Way Pipes

(Midwestern Consulting 1992)
Nail in Iron
Spike N/S U.P. N88°W 28.25
PK S/S 6" Oak EAST 35.75

(Glen Richard 1992)
3/4" Iron Pipe
Double head Nail in E. Pole
S20°W 115.20

(Atwell-Hicks 1993)
3/4" Iron Pipe
Utility Pole S15°E 115.18 to Nail
Utility Pole N81°W 27.86 to Nail
Utility Pole N75°E 63.92 to Nail
Fiber Optic Marker N28°W 72.26 to N.E. Face

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron Pipe 4" below gravel surface with bricks 12" below gravel surface. There was no other pipe below the 3/4" Iron Pipe. Set Aluminum Washtenaw County Remonumentation Cap on existing Iron Pipe and adjusted to 6" below gravel surface.

APPROVED

DATE 11/21/94

CO. REP. K

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" Iron Pipe with Aluminum Washtenaw County Remonumentation Cap
6" below Gravel Surface
2" Iron Pipe WEST 33.00
Utility Pole N85°W 27.70 to Nail W/W.C.R. Tag in N. Side
Utility Pole S15°E 115.20 to Nail W/W.C.R. Tag in E. Side
Utility Pole N75°E 63.95 to Nail W/W.C.R. Tag in N. Side
Fiber Optic Marker N35°W 72.22 to Nail W/W.C.R. Tag in NE Side

10" Poplar N35°E 37.40 to Nail
W.W.C.R. Tag in NW Side
Fiber Optic Marker S80°E 47.42 to Nail W/W.C.R. Tag in S Side

I conclude that after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by Thomas L. Sutherland Date December 14, 1994
Surveyor's Michigan License No. #24620

