

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

COMMISSION

COPY

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED
WASHTENAW COUNTY, MI

FEB 1 8 59 AM '95

PEGGY M. HAINES
COUNTY CLERK/REGISTER

copy

For corners in

<u>Washtenaw</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>7E</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 390 RM
COPY
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Thomas L. Sutherland in a field survey on November 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(W.C.R.C. 1935)

Found 2 pieces of angle iron in the center of what was an old wood stake. Re-set with Iron Pipe, Stones and Bricks.

(Atwell-Ricks 1980)

1" Iron Pipe
12" R. Pine S30°W 71.0
10" R. Pine S35°W 59.4
14" R. Pine S45°W 47.8
14" R. Pine S60°W 81.8
14" Ash N15°W 108.0

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" Cast Iron Pipe, Stones and Bricks 6" below Gravel Surface. Re-set with 1" x 24" Iron Pipe with aluminum Washtenaw County Remonumentation Cap 6" below Gravel Surface.

APPROVED

DATE 11/28/94

CO. REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1" x 24" Iron Pipe with Aluminum Washtenaw County Remonumentation Cap
- Telephone Pole S40°E 30.25 to
- 16" Pine S30°W 71.00 to Nail
W/W.C.R. Tag in S.E. Side
- 12" Spruce S35°W 59.00 to Nail
W/W.C.R. Tag in S.E. Side
- 16" Pine S45°W 47.72 to Nail
W/W.C.R. Tag in N.W. Side
- 18" Pine S60°W 81.80 to Nail
W/W.C.R. Tag in N.W. Side
- 22" Ash N06°W 107.91 to Nail
W/W.C.R. Tag in East Side
- Telephone Pole N55°W to Nail
W/W.C.R. Tag in S.W. Side

I conclude that after careful study of record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner.

Signed by Thomas L. Sutherland
Surveyor's Michigan License No. #24620



Date December 13, 1994