

SURVEY &
REMONUMENTATION

MAY - 1 1995

COMMISSION

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
WASHTENAW COUNTY, MI

FEB 1 9 01 AM '95

PEGGY M. NAINES
COUNTY CLERK/REGISTER

For corners in

Washtenaw (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>7E</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

-COPY-

LIBER

1 PAGE 395 RM
COPY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Thomas L. Sutherland in a field survey on November 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(Glen Richard #13040 - 1972)
3/4" Galvanized Pipe
Nail & Washer in 20" Oak
N80°W 34.17
Nail & Washer in 12" Oak
N40°W 39.55
Nail & Washer in 12" Oak
N40°E 48.47
End Post - Fence E/W & N
NORTH 3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Galvanized
Iron Pipe in approximate
fence lines (in poor repair)
North-East and West. Set
1" x 24" Iron Pipe with
Aluminum Washtenaw County
Remonumentation Cap over
existing 1/2" Galvanized
Iron Pipe.

APPROVED

DATE 11/28/94
CO. REP. K

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" x 24" Iron Pipe with Aluminum Washtenaw County Remonumentation Cap
36" Oak N85°W 33.97 to Nail
W/W.C.R. Tag in N. Side
24" Oak N50°W 39.55 to Nail
W/W.C.R. Tag in N.E. Side
10" Multiple Maple N88°W 5.09
to Nail W/W.C.R. Tag in
S. Side
6" Oak N15°E 21.72 to Nail
W/W.C.R. Tag in E. Side
4" Oak N10°W 19.84 to Nail
W/W.C.R. Tag in W. Side
10" Oak EAST 9.70 to Nail W/W.C.R.
Tag in N. Side

I conclude that after careful
study of the record documentation
and field observations, that this
corner is accepted as the best
available evidence of the position
of the original corner.

Signed by Thomas L. Sutherland
Surveyor's Michigan License No. #24620

Date

December 13, 1994

